

ACTIVITY NO.	ACTIVITY	RESPONSIBILITY	LOGICAL RELATIONSHIP WITH ACTIVITY NO.
1	Investigation phase	Karina	
2	Ordering materials	Karina	1
3	Material delivery	Victor	2
4	Receipt of materials, including assembly instructions and scale drawing for digging holes.	Victor	3
5	Digging four holes	Victor	4
6	Putting posts into the holes	Victor	5
7	Mounting the foundation on the posts	Victor	6
8	Assembling the front gable	Karina	4
9	Assembling the rear gable	Karina	4
10	Assembling the two sides	Victor	4
11	Mounting the four sides on the foundation	Victor	7, 8, 9, 10
12	Assembling the roof	Victor	11
13	Mounting hinges and frame	Victor	11
14	Assembling the door	Victor	4
15	Adjusting the door	Victor	13, 14
16	Assembling and mounting windows	Victor	12
17	Inserting glass	Karina	16
18	Tightening assemblies	Victor	15,17
19	Laying flagstones	Victor	17
20	Installing capillary boxes	Karina	19
21	Installing bench	Victor	19
22	Installing shelves	Victor	19
23	Installing thermometer	Karina	19
24	Installing watering unit	Victor	19

FIGURE 4.47
List of activities with dependencies.